



Typical* Automatic Transfer Switch Relay & Sequence Of Operation***

Created By "Custom Marine Services"



- * Typical...
1. DPDT
 2. Coil: 110V Dc
 3. Timer Pcb Input: 120V Ac
 4. Timer Pcb Output: 95 - 135V Dc
 5. Contact Rating: 30 Or 50 Amps
 - 6.



**** RELAY OPERATION... Std Factory Wiring...**

1. Shore power is "default". Shore power enters terminal #8, passes thru NC contact to terminal #4 and exits to load panel!
2. Generator is started... Power enters terminal #6, passes **to** NO contact & timer (starting countdown). At the end of countdown NC contact opens interrupting shore power & NO contact closes allowing gen power to pass thru to terminal #4 and exit to load panel...

NOTE: By "reducing the electrical loads" *** before starting the GENERATOR will extend the life and reduce maintenance on the ATS and generator.

***** SUB NOTE:** Generators not performing at peak performance may not be able to stabilize under heavy starting loads causing voltage sags / surges lower or higher than the system or equipment design.

